

- 1. BASE OF FABRIC SHALL BE BURIED AT LEAST 1' BELOW GROUND SURFACE AND BACKFILLED WITH CRUSHED STONE OR COMPACTED MATERIAL
- 2. WIRE MESH FENCE MAY BE USED TO SUPPORT FABRIC. TOP OF FENCE SHOULD BE LEVEL WITH FRAME AND BOTTOM BURIED 6" BELOW GROUND.
- 3. MAY BE NECESSARY TO BUILD A TEMPORARY DIKE ON DOWN-SLOPE SIDE OF STRUCTURE TO PREVENT BYPASS FLOW.
- 4. STRAW BALES OR GRAVEL FILLED FILTER BAGS MAY BE USED IN LIEU OF FABRIC. IF STRAW BALES ARE USED, TWO 4' (MINIMUM) LONG, 2" X 2" HARDWOOD STAKES SHALL BE DRIVEN THROUGH EACH BALE AND SET BACK 12" TO 24" FROM INLET. IF FILTER BAGS ARE USED, PLACE BAGS SUCH THAT NO GAPS ARE EVIDENT.

AREA INLET PROTECTION

GENERAL NOTES:

1. ANY EROSION AND SEDIMENT CONTROL MEASURES INTENDED TO CONTROL EROSION OF AN EARTH DISTURBANCE OPERATION SHALL BE INSTALLED BEFORE ANY EARTH DISTURBANCE OPERATIONS TAKE PLACE.

2. THE CONTRACTOR SHALL INSPECT THE LAND DISTURBANCE SITE AFTER EACH SIGNIFICANT RAINFALL EVENT WITHIN A 24—HOUR PERIOD AND ASSURE THAT ALL EROSION AND SEDIMENT CONTROL MEASURES ARE IN WORKING CONDITION PRIOR TO ANY FORECASTED RAINFALL, SEDIMENT REMOVAL AND ALL NECESSARY REPAIRS SHALL BE MADE TO MAINTAIN THE INTEGRITY OF THE EROSION AND SEDIMENT CONTROL MEASURES. SEDIMENT SHALL BE REMOVED ONCE IT REACHES HALF OF THE INSTALLED HEIGHT OF MEASURE.

3. THE CONTRACTOR SHALL MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING ALL PHASES OF CONSTRUCTION UNTIL OWNER ACCEPTS WORK AS COMPLETE. THE CONTRACTOR SHALL PROVIDE TEMPORARY SEEDING, BERMS, SILT FENCE, SEDIMENT TRAPS OR OTHER MEANS TO PREVENT SEDIMENT FROM REACHING STREAMS, PUBLIC RIGHT—OF—WAY OR ADJACENT PROPERTY.

4. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE REMOVED ONCE 70 PERCENT OF THE PERMANENT COVER IS ESTABLISHED.

5. THE CONTRACTOR SHALL TEMPORARILY SEED AND MULCH ALL DISTURBED AREAS IF THERE HAS BEEN NO CONSTRUCTION ACTIVITY ON THEM FOR A PERIOD OF 14 CALENDAR DAYS. IF THE ENGINEER DETERMINES THAT A SITE HAS A POTENTIAL FOR EROSION, STABILIZATION OF SOIL MAY BE REQUIRED. TEMPORARY SEED MIXTURE SHALL BE APPROVED BY THE ENGINEER OR AS FOLLOWS:

TYPE:

APPLICATION RATE: WINTER WHEAT

120 LBS PER ACRE 75 LBS PER ACRE

REPAIRS AND RESEEDING SHALL BE PERFORMED BY THE CONTRACTOR AT THE DIRECTION OF THE ENGINEER AT NO ADDITIONAL COST TO THE OWNER. IF VEGETATIVE MEASURES ARE NOT EFFECTIVE, NON-VEGETATIVE OPTION MAY BE REQUIRED.

					DRAWN BY:	DHS
					APP'D BY:	PDH
2	May 2015	Added & Updated Notes	DHS	JDH		
1	March 2013	Revised Notes	DHS	JDH		
NO.	DATE:	REVISION	BY:	APP'D		

SHAWNEE COUNTY, KANSAS PUBLIC WORKS DEPARTMENT COUNTY ENGINEER 1515 NW SALINE TOPEKA, KS 66618

(785) 233-7702



STANDARD DETAILS

GRAVEL FILTER BAGS-

SHALL BE APPROXIMATELY
24" LONG, 12" WIDE
HEIGHT OF BAGS SHOULD

NOT BE ABOVE THE TOP

PAVEMENT-

-SEDIMENT


FLOW-

HEIGHT OF BAGS SHOULD NOT BE-

ABOVE THE TOP OF THE INLET

OF THE INLET

INLET PROTECTION AND GENERAL NOTES (DT-020)



PLACE GRAVEL FILTER BAGS SUCH

-PLACE GRAVEL FILTER BAGS AT BOTH ENDS IN SUMP CONDITIONS TO PROVIDE TIGHT SEAL

THAT NO GAPS BETWEEN BAGS

OR AGAINST CURB ARE EVIDENT

FROM

-PLACE GRAVEL FILTER BAGS

SUCH THAT NO GAPS BETWEEN BAGS OR AGAINST CURB ARE EVIDENT

-GUTTER BUDDY OR OTHER APPROVED

MATERIAL

OPENING

CURB INLET SEDIMENT PROTECTION

NOTES:

1. OTHER APPROVED CURB INLET SEDIMENT FILTERS MAY BE USED.

2. IMMEDIATELY FOLLOWING INLET CONSTRUCTION AND PRIOR TO CONSTRUCTION OF CURB AND INLET THROAT, PROTECT INLET OPENING AROUND PERIMETER. SEE AREA INLET DETAIL THIS PAGE.

3. CONTRACTOR TO CLEAN OUT SEDIMENT AFTER EACH SIGNIFICANT RAINFALL EVENT.

4. DURING CONSTRUCTION GRAVEL FILTER BAGS SHALL BE REPLACED PRIOR TO DEGRADATION.

5. ANY SEDIMENT OR GRAVEL DEPOSITED IN INLET SHALL BE REMOVED PROMPTLY.

PLAN IN GRADE CONDITIONS

* - COARSE AGGREGATE 1/2"-1" DIAMETER

PLAN

PROFILE

PLAN '

SUMP CONDITIONS

DO NOT BLOCK INLET OPENING — STORMWATER MUST BE ALLOWED TO FLOW TO DRAIN AND NOT BYPASS TO DOWNSTREAM.

10' TYPICAL

EROSION & POLLUTION CONTROL

SHEET: PROJ.: